



# I-5 over 26th Ave Bridge Deck Replacement Project

Presenters: Jamie Miller, Josh Smith

Date: 2/7/25



# I-5 over 26th Ave Bridge Project

## Overview

- Project Length (0.3 miles)
- Classified as Urban Interstate
- Designated Reduction Review Route
- Federally Designated Truck Route
- AADT = 131,000
- Posted Speed: 55MPH
- Estimate cost of project \$11 mil



# Initial Concept Risks




- Staging
- Water Quality Facility
- Right-of-Way Impacts
- PBOT project on SW 26<sup>th</sup> Way



# Initial Concept Construction Staging

## Bridge Work within the Project Limits:

- Demolish existing three span bridge, construct single span bridge
- Completed in 3 stages




# VE (Value Engineering) Study - Project Overview



- Existing bridge is cracking and does not meet seismic design standards.
- Replace existing I-5 bridge with minimal impact to the travelling public.
- Project to be completed before Rose Quarter and Southwest Corridor construction starts.
- \$19,118,000 construction cost (biddables only – no inflation) Adding inflation and CE – \$26.2 M.
- 36 months to construct.

# VE Alternative 1.4

<b>Cost Savings:</b>	<b>\$9,320,000</b>
<b>Change in Schedule:</b>	<b>4-month reduction</b>



# Contractor Constructability Review



## 1:1 Sessions with Contractors

These 1:1 constructability focused sessions were conducted January 11th, 12th, & 24th, 2022 with 7 Contractors, select members of the design team, and members of the Statewide Project Delivery Branch.





# I-5 Over 26<sup>th</sup> Ave Constructability Review Summary


The Design team met with 7 different contractors with expertise in the following:

- Bridge demolition
- Micropile installation
- Bridge construction
- Pavement construction
- Retaining wall construction
- Low Density Cellular Concrete (LDCC)



# I-5 Over 26<sup>th</sup> Ave Replacement - Project Concept after @CCR

- Construct buried precast slab structure underneath existing I-5 bridge
- Switch from Soldier pile wall to MSE walls
- Backfill with low-density cellular concrete (LDCC)
- Remove existing structure and pave full depth ACP w/ Temp Wearing Course and aggregate in
- 56-hour weekend closure of I-5



# Summary of Discussions

## Significant Risks Identified

---

- **Threat** – Coordinating closure with WSDOT, PBOT, Freight/ Mobility, Emergency Services, and numerous other stakeholders.
- **Threat** – If equipment failure during closure weekend occurs then the closure window may be missed.
- **Threat** – If aggregate and material import is restricted due to congestion, then closure window may be missed.
- **Threat** – Timber piling/falsework obstructing micropile installation. Recommended response is to modify pile layout and allow flexibility.
- **Threat** – MPCO overlay may crack under movement. Recommended response to specify a more flexible product to seal slabs
- **Threat** – Precast slabs cost have escalated substantially and could take 6 months longer than typical to procure.

# Summary of Discussions

## Significant Advantages Identified

---

- **Opportunity** – Allow 3” to 15” processed bridge debris as stone embankment/sub-base.
- **Opportunity** – Provide staging/stockpile area and allow off-road haul trucks which can haul significantly more material minimizing trips.
- **Opportunity** – Change soldier pile wall to MSE wall
- **Time** – Completion of structure over one weekend rather than an additional 4 months of staged construction minimizing impact to the travelling public.
- **Safety** – Increased safety for construction crews, inspection staff, and the travelling public.



CROSSING  
ROADWAY

Sep 15, 2023 at 1:27:28 PM  
SW Barbur Ct



Jan 31, 2024 at 11:06:02 AM  
8920 SW 26th Ave



Jun 15, 2023 at 4:31:32 PM  
8943 SW 26th Ave










Apr 1, 2024 at 10:29:37 AM  
2701 SW Spring Garden St



Apr 1, 2024 at 10:30:18 AM  
I-5 S




# Preparations leading up to Full Closure

- Outreach to the public for upcoming closure included
  - Email to ODOT subscribers
  - Social and Local news media
  - Mailers, and community engagement.
- Coordination efforts with:
  - WSDOT, PBOT, Freight Mobility,
  - 50+ PCMS', VMS



# Construction and I-5 Closure Highlights

- Full 56 hour I-5 Closure implemented starting 9pm on June 28.
- Contractor was able to provide access to peds and bikes during construction, rather than providing a shuttle around the project at a cost savings of approximately \$17K.
- Work completed and closure lifted in 54 hours, 2 hours early.
- Construction office did not observe any severe traffic conditions on main detour route of 99W (Barbur Blvd)
- Original Cost \$11.1 Mill. vs Final Cost w/ CCOs.
- \$11.1 Mill.
- DBE Goal Org. 6.31% vs Final 7.93%.



# Benefits of the I-5 Closure

---

- Able to limit the overall impact to the travelling public. 56 hour closure vs. an additional 4 months of staged construction.
- Increased safety to contractor, inspection staff, and travelling public.
- Cost savings to the taxpayers – Approximately \$9M utilizing a 56 hour full closure vs staged construction.
- ODOT able to perform secondary preventative maintenance on items not related to the project but within the closure limits.
- Reduced waste and emissions by not constructing a temporary detour structure and re-using demolished bridge waste as roadway fill.

# Project Awards

---

- ACEC Oregon (American Council of Engineering Companies of Oregon) - Project of the Year.
- PCI (Precast/ Prestressed Concrete Institute) – 2025 PCI Design Award - Transportation Award: Bridge with a Main Span up to 75 Feet.
- ITE (Institute of Transportation Engineers) 2024 Oregon Transportation Project of the Year.



Questions?